



Calcasieu Parish Sheriff's Office

TONY MANCUSO, SHERIFF AND EX-OFFICIO TAX COLLECTOR

Parish of Calcasieu • 5400 E. Broad Street • Lake Charles, LA 70615
Phone (337) 491-3700 • Fax (337) 494-4522

February 18, 2021

ADDENDUM #1

K-9 Building (Asset #001-010)

NOTE: The following clarifications, changes, additions or deletions to the Specifications shall hereby be incorporated into the Contract Documents for the above referenced project. This addendum supersedes all contrary and conflicting information contained in previous Addenda, Drawings and Specifications and are hereby amended. Bidders shall acknowledge receipt of all Addenda in the space on the Bid Form.

K-9 Building

Lobby

General

- | | |
|---|-----------|
| 1. Rewire ALL wiring - average residence - copper wiring | 345.65 SF |
| 1. Networking cable/outlets - Category 5
Replace the damaged CAT 5 wires | 56.00 LF |
| 2. Seal/prime then paint the ceiling (2 coats) | 345.65 SF |

HVC Accessories

- | | |
|-------------------------------|-----------|
| 3. Paint the walls - one coat | 658.67 SF |
|-------------------------------|-----------|

Trim Work

- | | |
|------------------------------------|-----------|
| 4. Install Baseboard - 3 1/4" | 82.33 LF |
| 5. Paint baseboard - two coats | 82.33 LF |
| 6. Glue down vinyl - heavy traffic | 345.65 SF |

Office 1

General

- | | |
|---|-----------|
| 8. Rewire ALL wiring- average residence - copper wiring | 146.09 SF |
| 9. Networking cable/outlets - Category 5
Replace the damaged CAT 5 wires | 64.08 LF |
| 10. Seal/prime then paint the ceiling (2 coats) | 146.09 SF |

Trim Work

- | | |
|---------------------------------|----------|
| 11. Baseboard - 3 1/4" | 50.33 LF |
| 12. Paint baseboard - two coats | 50.33 LF |

Contractor is responsible to field verify all dimensions and penetrations.

Office 2

General

13. Rewire ALL wiring - average residence - copper wiring	143.41 SF
14. Networking cable/outlets - Category 5 Replace the damaged CAT 5 wires	64.08 LF
15. Seal/prime then paint the ceiling (2 coats)	143.41 SF

Trim Work

16. Baseboard - 3 1/4"	50.00 LF
17. Paint baseboard - two coats	50.00 LF

Office 3

General

18. Rewire ALL wiring - average residence - copper wiring	172.90 SF
19. Networking cable/outlets - Category 5 Replace the damaged CAT 5 wires	64.08 LF
20. Seal/prime then paint the ceiling (2 coats)	172.90 SF

Trim Work

21. Baseboard - 3 1/4"	53.67 LF
22. Paint baseboard - two coats	53.67 LF

Utility Room

General

23. Rewire ALL wiring - average residence - copper wiring	239.14 SF
24. Networking cable/outlets - Category 5 Replace the damaged CAT 5 wires	69.33 LF
25. Seal/prime then paint the ceiling (2 coats)	239.14 SF

Trim Work

26. Paint baseboard - two coats	70.00 LF
---------------------------------	----------

Bathroom

General

27. Rewire ALL wiring - average residence - copper wiring	72.80 SF
28. 5/8" drywall - hung, taped, floated, ready for paint	72.80 SF
29. Remove & Replace Light Fixture	1.00 EA

HVC Accessories

30. Heat/AC register – Mechanically attached	1.00 EA
31. Batt insulation - 4" - R13 – unfaced	152.00 SF
32. Seal/prime then paint the walls (2 coats)	304.00 SF

Sink

33. Remove & Replace Plumbing fixture supply line	2.00 EA
34. Remove & Replace P-trap assembly - ABS (plastic)	1.00 EA

Contractor is responsible to field verify all dimensions and penetrations.

35. Remove & Replace Angle stop valve 2.00 EA

Bathroom Accessories

36. Remove & Replace Mirror - 1/4" plate glass 8.00 SF

37. Remove & Replace Paper towel dispenser 1.00 EA

Bathroom Closet

General

38. Rewire **ALL** wiring - average residence - copper wiring 11.92 SF

39. 5/8" drywall - hung, taped, floated, ready for paint 113.33 SF

40. Seal/prime then paint the walls (2 coats) 113.33 SF

41. Remove & Replace Light Fixture 1.00 EA

Exterior

Doors

42. Remove & Replace Exterior door - metal – insulated- flush or panel style 2.00 EA

43. Remove & Replace Wrap wood door frame & trim with aluminum (PER LF) 67.00 LF

44. Remove & Replace Aluminum window, single hung 9-12 sf (2 pane) 1.00 EA

45. Remove & Replace Meter base and main disconnect- 200 amp 1.00 EA

46. Remove & Replace Rigid conduit, 3" 10.00 LF

47. Remove & Replace Circuit breaker – main disconnect - 150 to 200 amp 1.00 EA

48. Remove & Replace Exterior wall pack - Sodium – 250 watt 2.00 EA

49. Remove & Replace Spotlight fixture – double 8.00 EA

50. Remove & Replace - annunciator panel 1.00 EA

51. Remove & Replace Exterior faucet / hose bibb 1.00 EA

52. Remove & Replace Concrete slab on grade - 4" - finished in place 600.00 SF

53. Remove & Replace Concrete slab reinforcement - #3 (3/8") - grid, 24" ea way 600.00 SF

Contractor is responsible to field verify all dimensions and penetrations.

END OF ADDENDUM